
STORMWATER MAINTENANCE PLAN

for

University Center Phase 2 Addition and Renovation Seton Hall University Township of South Orange Village Essex County, New Jersey

Prepared For:

Seton Hall University
400 South Orange Avenue
South Orange, New Jersey 07079

Prepared By:

Langan Engineering and Environmental Services, Inc.
300 Kimball Drive
Parsippany, New Jersey 07054



Leonard D. Savino, P.E.
NJ Professional Engineer License No. 39238

17 December 2020
Langan Project No. 100898001

LANGAN

TABLE OF CONTENTS

I. INTRODUCTION	Page 1
II. PROJECT DESCRIPTION.....	Page 1
III. STORMWATER MAINTENANCE OBJECTIVE	Page 2
IV. MAINTENANCE OF CONVEYANCE SYSTEMS	Page 2
V. MAINTENANCE OF SUBSURFACE DETENTION BASIN	Page 3
VI. ANNUAL EVALUATION OF THE EFFECTIVENESS OF THE PLAN	Page 4

DRAWINGS

CS101 – SITE PLAN
CG101 – GRADING PLAN
CG102 – DRAINAGE PLAN
CS501 – DETAILS I
CS502 – DETAILS II

ATTACHMENTS

- 1. MAINTENANCE INSPECTION CHECKLIST FOR CONVEYANCE SYSTEMS**
- 2. MAINTENANCE LOG FOR CONVEYANCE SYSTEMS**
- 3. MAINTENANCE CHECKLIST FOR UNDERGROUND DETENTION FACILITY**
- 4. MAINTENANCE LOG FOR UNDERGROUND DETENTION FACILITY**
- 5. RECORD OF ANNUAL EVALUATION OF THE EFFECTIVENESS OF THE PLAN**

I. INTRODUCTION

The New Jersey Administrative Code NJAC 7:8-5.8 entitled "Maintenance Requirements" sets forth rules and refers to the New Jersey Stormwater Best Practices Manual (the BMP manual) dated February 2004 by the New Jersey Department of Environmental Protection (NJDEP). Chapter 8 of the BMP manual entitled "Maintenance and Retrofit of Stormwater Management Measures" specifically addresses the requirements for maintenance of a major development. Major development is defined in the aforementioned administrative code as any development that provides for ultimately disturbing one or more acres of land or increasing the amount of impervious surface by one quarter of an acre or more. This report was prepared to address the maintenance component of the herein described development to ensure the effective, efficient, and enduring service of the associated stormwater measures. This plan contains preventative and corrective maintenance tasks and procedures.

The party responsible for the preventative and corrective maintenance of the stormwater measures described herein is:

Seton Hall University
c/o Victoria Pivovarnick
Facilities Engineering Department
400 South Orange Avenue
South Orange, New Jersey 07079
Telephone number: (973) 761-9454

II. PROJECT DESCRIPTION

The proposed development of the subject property will consist of selective demolition of portions of the existing University Center building, including their associated site and utility infrastructure. The development also includes the construction of three new additions to the University Center including the northern lower level addition (Constructed in 2018), the western façade and entry addition, and the eastern entry addition. Other construction will include site infrastructure within the disturbed area, including reconstructing sidewalks and landscaping. The University Center will also require multiple utility relocations as well as new below-grade utilities to support the building additions, including stormwater conveyance sewers, detention basins, sanitary sewers, water mains, electric and telecommunications conduit and steam lines.

Proposed utilities will also include the extension and interconnection of the existing network of water mains within the site; new sanitary sewers, which will connect to the existing sanitary sewer system on-site; and a new storm sewer system on-site, which will be connected to new storm detention basins under the landscaped area to the north of the University Center and near the eastern entry addition. The on-site stormwater management and conveyance systems have been designed in accordance with the Township of South Orange Village Stormwater Control Ordinance and the Stormwater Management Regulations issued by the New Jersey Department of Environmental Protection (NJDEP).

The proposed development will include a system of catch basins, manholes, underground

conveyance pipes to collect and convey the stormwater to the proposed subsurface detention basins.

III. STORMWATER MAINTENANCE OBJECTIVE

The stormwater systems proposed for this development are intended to attenuate and convey the stormwater from the development. This maintenance plan is prepared to ensure the systems in place are operating efficiently and reliably. The responsible party shall ensure the long-term/perpetual operation, maintenance, repair, and safety of the stormwater management facilities. In the event that the stormwater management conveyance system becomes a danger to public safety or public health, or if it is in need of maintenance, the municipality shall so notify the responsible person in writing. If for reasons of safety there is need for immediate action, the responsible person shall act forthwith to remove the danger.

Maintenance procedures are required to maintain the intended operation and safe condition of the stormwater management facility by reducing the occurrence of problems and malfunctions. To be effective, maintenance shall be performed on a regular basis and include such routine procedures as training of staff, periodic inspections, silt and debris removal and disposal, control of mosquitoes and other insects, and review of maintenance and inspection work to identify where the maintenance program could be more effective. The required inspections are to be conducted only by properly trained individuals, including confined space entry training and certification. As per N.J.A.C. 7:8-5.8(f), the person responsible for maintenance shall maintain a detailed log of all preventative and corrective maintenance for the structural stormwater management measures incorporated into the design of the development, including a record of all inspections and copies of all maintenance-related work orders. The person with maintenance responsibility must retain and, upon request, make available the maintenance plan and associated logs and other records for review by a public entity with administrative, health, environmental, or safety authority over the site.

Repair procedures are required to correct a problem or malfunction at a stormwater management facility and to restore the facility's intended operation and safe condition. Based upon the severity of the problem, repairs shall be performed on an as-needed or emergency basis and may include such procedures as structural repairs, mosquito control, removal of debris, sediment and trash which threaten discharge capacity, erosion repair, snow and ice removal and restoration of vegetation.

In the event that the stormwater management conveyance system becomes a danger to public safety or public health, or if it is in need of maintenance, the municipality may notify the responsible person in writing. Upon receipt of that notice, the responsible person shall have fourteen (14) days to initiate maintenance and repair of the system in a manner that is approved by the municipal engineer or his designee. If the responsible person fails or refuses to perform such maintenance and repair, the municipality may immediately proceed to do so and shall bill the cost thereof to the responsible person.

IV. MAINTENANCE OF CONVEYANCE SYSTEMS

The proposed conveyance systems have adequate access for inspection and/or maintenance. The use of the proposed conveyance systems is necessary to manage runoff and is consistent with the community's surroundings for this area.

All conveyance systems including inlets, manholes and pipes are expected to receive and/or accumulate debris and sediment. These systems must be inspected quarterly for clogging, excessive debris and sediment accumulation as well as after every storm exceeding one inch of rainfall. Sediment removal should take place when all runoff has drained from the conveyance network and the systems are reasonably dry. Disposal of debris, trash, sediment, and other waste material should be done at suitable disposal/recycling sites and in compliance with all applicable local, state, and federal waste regulations.

All structural components must be inspected quarterly for cracking, subsidence, breaching, wearing, and deterioration. The condition of surrounding and above lying materials shall be inspected for evidence of potential failures or deterioration.

Maintenance of the conveyance system would require a minimum of two people. The routine equipment expected to be utilized for the maintenance tasks may include a jet vacuum vehicle, shovels, lighting equipment and a wheel barrel or truck for the hauling off of debris. Water, mosquito control chemicals, and concrete repair materials may also be required depending on the condition of the structure. Refer to manufacturer's maintenance/repair specifications for ADS manholes and risers. The cost to perform routine maintenance tasks including removal of debris, sediment and trash is estimated to be no more than \$5,000/year for the onsite proposed systems.

Related inspection and maintenance forms for this work are located in the appendix of this report.

V. MAINTENANCE OF SUBSURFACE DETENTION BASINS

The detention systems, including the outlet control structure and pipes, are expected to receive and/or accumulate debris and sediment on occasion. These systems should be inspected quarterly for clogging and excessive debris and sediment accumulation as well as after every storm exceeding one inch of rainfall. Accumulated sediment removal should take place when all runoff has drained from the subsurface detention systems and the systems are reasonably dry. Disposal of debris, trash, sediment, and other waste material shall be done at suitable disposal/recycling sites and in compliance with all applicable local, county, State and federal waste regulations.

All structural components must be inspected quarterly for cracking, subsidence, breaching, wearing, and deterioration. The condition of surrounding above-ground areas shall be inspected for evidence of potential failures or deterioration of buried stormwater facilities.

The routine equipment expected to be utilized for the maintenance tasks may include a jet vacuum vehicle, shovels, lighting equipment, and a wheel barrow or truck for the hauling of debris. Water and concrete repair materials may also be required depending on the condition of the structures.

No specialty equipment should be needed. Follow standard manufacturer's instructions or user manuals for these components. The cost to perform routine maintenance tasks including removal of debris, sediment and trash is estimated to be no more than \$5,000/year for the onsite proposed stormwater detention systems.

Related inspection and maintenance forms for this work are located in the appendix of this report.

VI. ANNUAL EVALUATION OF THE EFFECTIVENESS OF THE PLAN

As per N.J.A.C. 7:8-5.8(g), the person responsible for maintenance shall evaluate the effectiveness of the maintenance plan at least once per year and adjust the plan as needed. The annual assessment shall be documented. Records must be retained and be available upon request for review by a public entity with administrative, health, environmental, or safety authority over the site


The responsible party should evaluate the effectiveness of the maintenance plan by comparing the maintenance plan with the actual performance of the maintenance. The items to evaluate may include, but not limited to,

- Whether the inspections have been performed as scheduled;
- Whether the preventive maintenance has been performed as scheduled;
- Whether the frequency of preventative maintenance needs to increase or decrease;
- Whether the planned resources were enough to perform the maintenance;
- Whether the repairs were completed on time;
- Whether the inspection, maintenance, and repair records have been kept.

If actual performance of those items has deviated from the maintenance plan, the responsible party should find the causes and implement solutions in a revised maintenance plan.

An annual evaluation form is located in the appendix of this report.

DRAWINGS



- ### GENERAL NOTES
- THESE PLANS REPRESENT OVERALL SITEWORK IMPROVEMENTS REQUIRED FOR PROJECT CONSTRUCTION. THE WORK TO BE PERFORMED IS SHOWN ON THE DRAWINGS AND IS DESCRIBED IN THE CONTRACT SPECIFICATIONS. THE CONTRACTOR IS RESPONSIBLE FOR MEANS AND METHODS OF CONSTRUCTION. AS SUCH, THESE PLANS DO NOT COMPLETELY REPRESENT ALL SPECIFIC SITE DETAILS OF INSTALLATION REQUIRED FOR SITEWORK CONSTRUCTION. CONTRACTOR IS RESPONSIBLE TO PROVIDE ALL IMPROVEMENTS REQUIRED TO ACHIEVE CONSTRUCTION DEPICTED ON THESE PLANS.
 - THE CONTRACTOR SHALL ACCEPT THE SITE AS IS. THE CONTRACTOR SHALL ASSESS CONDITIONS, AND THE KIND, QUALITY AND QUANTITY OF WORK REQUIRED. THE OWNER MAKES NO GUARANTEE IN REGARD TO THE ACCURACY OF ANY AVAILABLE INFORMATION WHICH WAS OBTAINED DURING INVESTIGATIONS. THE CONTRACTOR SHALL MAKE A THOROUGH SITE INSPECTION IN ORDER TO FIELD CHECK EXISTING SITE CONDITIONS, CORRELATE CONDITIONS WITH THE DRAWINGS AND RESOLVE ANY POSSIBLE CONSTRUCTION CONFLICTS WITH THE OWNER AND ENGINEER PRIOR TO COMMENCEMENT OF WORK. THE CONTRACTOR SHALL MAKE ADDITIONAL TOPOGRAPHIC SURVEYS AS DEEMED NECESSARY, PROVIDED THEY ARE COORDINATED WITH THE OWNER. ANY CONDITIONS DETERMINED BY THE CONTRACTOR THAT DIFFER FROM THE INFORMATION SHOWN ON THE DRAWINGS THAT ARE NOT BROUGHT TO THE ATTENTION OF THE OWNER AND ENGINEER PRIOR TO THE START OF WORK SHALL NOT BE CONSIDERED GROUNDS FOR ADDITIONAL PAYMENT OR CHANGES TO THE CONTRACT DURATION, OR ANY OTHER CLAIMS AGAINST THE OWNER OR OWNER'S ENGINEER.
 - THE CONTRACTOR SHALL, WHEN HE/SHE DEEMS NECESSARY, PROVIDE WRITTEN REQUESTS FOR INFORMATION (RFI) TO THE OWNER AND ENGINEER PRIOR TO THE CONSTRUCTION OF ANY SPECIFIC SITEWORK ITEM. THE (RFI) SHALL BE IN A FORM ACCEPTABLE TO OWNER AND ENGINEER AND SHALL ALLOW FOR A MINIMUM OF TWO WORK DAYS OR ADDITIONAL REASONABLE TIME FOR A WRITTEN REPLY. RFI SHALL BE NUMBERED CONSECUTIVELY BY DATE SUBMITTED. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR SITEWORK ITEMS CONSTRUCTED DIFFERENTLY THAN INTENDED OR AS DEPICTED ON THE PLANS.
 - INFORMATION RELATED TO ELEVATIONS AND PROPOSED UTILITIES (SUCH AS ROADWAY GRADES, INVERT ELEVATIONS, RIM ELEVATIONS, GRATE ELEVATIONS, BUILDING FINISHED FLOOR ELEVATIONS, ETC.) MAY BE FOUND IN MORE THAN ONE LOCATION ON THE DRAWINGS. CONTRACTOR SHALL SPECIFICALLY REVIEW ALL PLANS, PROFILES AND ANY INFORMATION/TABLES FOR CONSISTENCY PRIOR TO CONSTRUCTION. ANY INCONSISTENCIES OR DISCREPANCIES THAT ARE FOUND SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE OWNER'S ENGINEER IN WRITING PRIOR TO CONSTRUCTION.
 - THERE ARE ADDITIONAL NOTES, SPECIFICATIONS AND REQUIREMENTS CONTAINED ON SHEETS THROUGHOUT THE PLAN SET AND AVAILABLE REFERENCES TO SPECIFICATIONS FROM APPLICABLE GOVERNING AUTHORITIES AND INDUSTRY STANDARDS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN, REVIEW AND ADHERE TO ALL APPLICABLE REQUIREMENTS.
 - CONTRACTOR IS SPECIFICALLY CAUTIONED THAT ALL CONSTRUCTION STAKEOUT FOR THIS PROJECT MUST BE COMPLETED FROM THE SITE SPECIFIC SURVEY CONTROL (HORIZONTAL AND VERTICAL) UPON WHICH THE DESIGN IS BASED. THE CONTRACTOR SHOULD NOT RELY ON OR RE-ESTABLISH SURVEY CONTROL BY GPS OR OTHER METHODS FOR USE IN CONSTRUCTION STAKEOUT OR ANY OTHER PURPOSE FOR THIS PROJECT. ANY DISCREPANCIES BETWEEN THE EXISTING HORIZONTAL OR VERTICAL DATA SHOWN ON THESE DRAWINGS AND THAT ENCOUNTERED IN THE FIELD MUST BE REPORTED TO THE DESIGN TEAM PRIOR TO CONSTRUCTION FOR RESOLUTION.
 - CONTRACTOR SHALL SUBMIT SHOP DRAWINGS FOR ALL DRAINAGE AND UTILITY STRUCTURES AND MANUFACTURED PRODUCTS TO THE ENGINEER OF RECORD FOR REVIEW AND APPROVAL PRIOR TO COMMENCING WITH CONSTRUCTION.
 - SEE ARCHITECTURAL DRAWINGS FOR EXACT BUILDING DIMENSIONS AND DETAILS CONTIGUOUS TO THE BUILDING, INCLUDING BUILDING ENTRANCES, STAIRWAYS, UTILITY PENETRATIONS, CONCRETE DOOR PADS, BOLLARDS, ETC.
 - SYMBOLS AND LEGENDS OF PROJECT FEATURES ARE GRAPHIC REPRESENTATIONS AND ARE NOT NECESSARILY SCALED TO THEIR ACTUAL DIMENSIONS OR LOCATIONS ON THE DRAWINGS.
 - CONTRACTOR SHALL NOT RELY SOLELY ON ELECTRONIC VERSIONS OF PLANS, SPECIFICATIONS, AND DATA FILES THAT ARE OBTAINED FROM THE DESIGNERS, BUT SHALL VERIFY LOCATION OF PROJECT FEATURES IN ACCORDANCE WITH THE PAPER COPIES OF THE PLANS AND SPECIFICATIONS THAT ARE SUPPLIED AS PART OF THE CONTRACT DOCUMENTS.
 - CONTRACTOR TO CONFIRM ALL ADA WORK IS PERFORMED IN ACCORDANCE WITH THE LATEST STANDARD AND REGULATIONS PER APPLICABLE TOWNSHIP OF SOUTH ORANGE, ESSEX COUNTY, STATE OF NEW JERSEY AND FEDERAL CODES.

NOTE:
NO CHANGES ARE PROPOSED TO THE UNIVERSITY'S EXISTING SOLID WASTE AND RECYCLING PLANS.

SIGN LEGEND

10 MINUTE PARKING	DO NOT ENTER
CUSTOM 12"x18"	RS-1 30"x30"
R3-1 24"x24"	RS-11 30"x24"
STOP	R1-1 30"x30"


LEGEND

PROPERTY LINE	PROPOSED BUILDING SETBACK LINE
PROPOSED BUILDING	PROPOSED BELGIAN BLOCK CURB
PROPOSED FLUSH BELGIAN CURB AT ADA RAMPS / DEPRESSED CURB AT DRIVEWAY RAMPS	PROPOSED RETAINING WALL
PROPOSED CONCRETE SIDEWALK	PROPOSED SIGN (SEE SIGN LEGEND)
PROPOSED BUILDING DOOR	PROPOSED PARKING COUNT

- ### REFERENCE NOTES
- EXISTING SURVEY AND TOPOGRAPHIC INFORMATION OBTAINED FROM A PLAN TITLED "PARTIAL TOPOGRAPHIC SURVEY - SETON HALL, PHASE 2" PREPARED BY LANGAN ENGINEERING AND ENVIRONMENTAL SERVICES, INC. ON 15 DECEMBER 2020.
 - PROPOSED BUILDING FOOTPRINT OBTAINED ELECTRONICALLY FROM CCH ARCHITECTS ON 15 DECEMBER 2020.
 - THE MERIDIAN OF THE SURVEY IS REFERENCED TO THE NEW JERSEY STATE PLANE COORDINATE SYSTEM NAD 83 (2011).
 - ELEVATIONS SHOWN ARE REFERENCED TO THE PLAN TITLED "UTILITY CLEARANCE SURVEY RESULTS, SETON HALL UNIVERSITY, SOUTH ORANGE, NJ PREPARED BY MIROSCAN, INC., DATED AUGUST 8, 2008".




Date	Description	No.
Revisions		




LEONARD D. SAVINO
PROFESSIONAL ENGINEER NJ LIC. No. 39238

LANGAN
Langan Engineering and Environmental Services, Inc.
300 Kimball Drive
Parsippany, NJ 07054
T: 973.560.4900 F: 973.560.4901 www.langan.com
NJ Certificate of Authorization No. 24G427996400


Project UNIVERSITY CENTER PHASE 2 RENOVATION & ADDITION SETON HALL UNIVERSITY 400 SOUTH ORANGE AVENUE BLOCK NO. 901, LOT NO. 3 TOWNSHIP OF SOUTH ORANGE VILLAGE ESSEX COUNTY NEW JERSEY	Drawing Title SITE PLAN	Project No. 100898001	Drawing No. CS101
Date 12/17/2020	Drawn By BMW	Checked By JED	




GRADING ENLARGEMENT 'B'



GRADING ENLARGEMENT 'C'



KEY MAP



GRADING ENLARGEMENT 'A'

LEGEND	
	PROPERTY LINE
	EXISTING MAJOR CONTOUR
	EXISTING MINOR CONTOUR
	PROPOSED MAJOR CONTOUR
	PROPOSED MINOR CONTOUR
	PROPOSED SPOT ELEVATION
	PROPOSED TOP/BOTTOM OF CURB ELEVATION
	LAWN/SIDEWALK ELEVATION AT CURB ELEVATION
	PROPOSED LOW POINT
	PROPOSED HIGH POINT
	PROPOSED FLOW DIRECTION
	PROPOSED RIDGE LINE
	PROPOSED DRAINAGE PIPE
	PROPOSED CATCH BASIN
	PROPOSED DRAINAGE MANHOLE

REFERENCE NOTES	
1.	EXISTING SURVEY AND TOPOGRAPHIC INFORMATION OBTAINED FROM A PLAN TITLED "PARTIAL TOPOGRAPHIC SURVEY SETON HALL, PHASE 2" PREPARED BY LANGAN ENGINEERING AND ENVIRONMENTAL SERVICES, INC. ON 15 DECEMBER 2020.
2.	PROPOSED BUILDING FOOTPRINT OBTAINED ELECTRONICALLY FROM CCH ARCHITECTS ON 15 DECEMBER 2020.
3.	THE MERIDIAN OF THE SURVEY IS REFERENCED TO THE NEW JERSEY STATE PLANE COORDINATE SYSTEM NAD 83 (2011).
4.	ELEVATIONS SHOWN ARE REFERENCED TO THE PLAN TITLED "UTILITY CLEARANCE SURVEY RESULTS, SETON HALL UNIVERSITY, SOUTH ORANGE, NJ PREPARED BY ENVIROMAX, INC., DATED AUGUST 8, 2008".


LANGAN
Langan Engineering and Environmental Services, Inc.
300 Kimball Drive
Parsippany, NJ 07054
T: 973.560.4900 F: 973.560.4901 www.langan.com
NJ Certificate of Authorization No. 24G24799640

Signature: *Leonard D. Savino* Date: 12/17/2020
LEONARD D. SAVINO
PROFESSIONAL ENGINEER NJ LIC. No. 39238

Project UNIVERSITY CENTER PHASE 2 RENOVATION & ADDITION SETON HALL UNIVERSITY 400 SOUTH ORANGE AVENUE BLOCK No. 901, LOT No. 3 TOWNSHIP OF SOUTH ORANGE VILLAGE ESSEX COUNTY NEW JERSEY		Drawing Title GRADING PLAN		Project No. 100898001		Drawing No. CG101	
Date 12/17/2020		Drawn By BMW		Checked By JED			


DRAINAGE STRUCTURE SCHEDULE	
Seton Hall University Center Phase 2	
Renovation & Addition	
Structure ID	Structure Type
YD-101	ZURN Z158 SQUARE DECK DRAIN
YD-102	ZURN Z158 SQUARE DECK DRAIN
YD-103	ZURN Z158 SQUARE DECK DRAIN
YD-104	ZURN Z158 SQUARE DECK DRAIN
YD-105	ZURN Z158 SQUARE DECK DRAIN
YD-106	ZURN Z158 SQUARE DECK DRAIN
YD-107	ZURN Z158 SQUARE DECK DRAIN
YD-108	ZURN Z158 SQUARE DECK DRAIN
YD-109	ZURN Z158 SQUARE DECK DRAIN
YD-110	15" NYLOPLAST DRAIN BASIN
YD-111	15" NYLOPLAST DRAIN BASIN
MH-101	4' I.D. CONCRETE MANHOLE
MH-102	6' I.D. CONCRETE MANHOLE
OCS-101	SEE DETAIL
YD-201	15" NYLOPLAST DRAIN BASIN
YD-202	ZURN Z158 SQUARE DECK DRAIN
YD-203	ZURN Z158 SQUARE DECK DRAIN
YD-204	ZURN Z158 SQUARE DECK DRAIN
YD-205	ZURN Z158 SQUARE DECK DRAIN
YD-206	ZURN Z158 SQUARE DECK DRAIN
STUB-201	STUB CONNECTION
STUB-202	STUB CONNECTION
OCS-201	SEE DETAIL
MH-301	4' I.D. CONCRETE MANHOLE

Note:
Contractor shall submit shop drawings to the engineer of record for review and approval prior to commencement of construction.





Project No. 10099001






© 2020 Langan



* Regularly furnished unless otherwise specified. **Note:** -DP and -90 option can not be specified together.

Zurn Industries, LLC Specification Drainage Operation 1801 Pittsburgh Avenue, Erie, Pa. U.S.A. 16502 Ph. 855-663-9876, Fax 814-454-7829 In Canada Zurn Industries Limited 9544 Nazbon Drive, Mississauga, Ontario L4V 1L2 Ph. 905-405-8272, Fax 905-405-1292 www.zurn.com	Rev. L Date: 09/25/2017 C.N. No. 137806 Prod./Dwg. No. Z158
---	--







PIPE INSTALLATION AND PAVEMENT RESTORATION

DOWNSPOUT CONNECTION

UTILITY CONNECTION TO EXISTING STRUCTURE

WATER MAIN CONNECTION

CLEAN OUT



WATER MAIN THRUST BLOCKS

WATER VALVE BOX

Date	Description	No.
Revisions		

Signature Leonard D. Savino Date 12/17/2020
LEONARD D. SAVINO
PROFESSIONAL ENGINEER NJ LIC. No. 39238

LANGAN
Langan Engineering and
Environmental Services, Inc.
300 Kimball Drive
Parsippany, NJ 07054
T: 973.560.4900 F: 973.560.4901 www.langan.com
NJ Certificate of Authorization No. 24A27996400

Project
**UNIVERSITY CENTER PHASE 2
RENOVATION & ADDITION
SETON HALL UNIVERSITY**
400 SOUTH ORANGE AVENUE
BLOCK NO. 901, LOT NO. 3
TOWNSHIP OF SOUTH ORANGE VILLAGE
ESSEX COUNTY NEW JERSEY

Drawing Title

**CONSTRUCTION
DETAILS III**

Project No.	100898001
Date	12/17/2020
Drawn By	BMW
Checked By	IED

Drawing No.

CS503

ATTACHMENTS

MAINTENANCE INSPECTION FOR CONVEYANCE SYSTEMS

**UNIVERSITY CENTER
SETON HALL UNIVERSITY
SOUTH ORANGE, NEW JERSEY**

**NOTE: INSPECTIONS TO BE EVALUATED DURING A
PERIOD OF DRY AND WARM WEATHER AND LOW TIDE
CONDITIONS AT THE PROJECT SITE**

Yes	No	Maintenance Evaluation	Action(s) Required if Answer "Yes"
<input type="checkbox"/>	<input type="checkbox"/>	Is there a buildup of sediment (in excess of 2 inches), trash, debris or any other stormwater pollution?	Remove sediment and evaluate on-site upstream systems. Dispose debris in accordance with local, state and federal requirements.
<input type="checkbox"/>	<input type="checkbox"/>	Is there standing water?	Evaluate downstream systems for clogging or trash sediment buildup.
<input type="checkbox"/>	<input type="checkbox"/>	Is there any structural failure?	Consult engineer to determine safety and/or stability of the system.
<input type="checkbox"/>	<input type="checkbox"/>	Are there visible signs of cracking, subsidence, erosion or deterioration of any of the storm conveyance systems?	Consult engineer to determine safety and/or stability of the system.
<input type="checkbox"/>	<input type="checkbox"/>	Are there any root intrusions or any other vegetation within catch basins, outlet control structures or storm manholes?	Remove roots and dispose vegetation in accordance with local, state and federal requirements.
<input type="checkbox"/>	<input type="checkbox"/>	Are ladder rungs in manholes or outlet structures damaged, missing or misaligned?	Repair or replace.
<input type="checkbox"/>	<input type="checkbox"/>	Are and covers or grates missing, damaged or only partially in place at any catch basin, outlet control structure or manhole?	Repair or replace.

MAINTENANCE CHECKLIST FOR UNDERGROUND DETENTION FACILITY

**UNIVERSITY CENTER
SETON HALL UNIVERSITY
SOUTH ORANGE, NEW JERSEY**

**NOTE: INSPECTIONS TO BE EVALUATED DURING A PERIOD OF
DRY AND WARM WEATHER AND LOW TIDE CONDITIONS AT THE
PROJECT SITE**

Yes	No	Maintenance Evaluation	Action(s) Required if Answer "Yes"
<input type="checkbox"/>	<input type="checkbox"/>	Is there a buildup of sediment (in excess of two inches), trash, debris or any other stormwater pollution within the header pipes, outlet structure or oversized manholes.	Remove sediment, trash, debris, etc. Dispose debris in accordance with local, state and federal requirements.
<input type="checkbox"/>	<input type="checkbox"/>	Is there any structural failure to the header and lateral pipes?	Consult engineer to determine safety and stability of the system.
<input type="checkbox"/>	<input type="checkbox"/>	Are there visible signs of cracking (wider than half an inch), damage or deterioration on the outlet structure or oversized manholes?	Consult engineer to determine safety and stability of the system.
<input type="checkbox"/>	<input type="checkbox"/>	Are there any signs of unusual color, odor or turbidity within the discharged water?	Evaluate upstream header pipes and structures for possible sediment, trash and debris. Cleanse system if any of the aforementioned obstructions are encountered. Dispose obstructions in accordance with local, state and federal requirements.
<input type="checkbox"/>	<input type="checkbox"/>	Are there root intrusions or any other plant growth occurring with the system(s)?	Remove vegetation and dispose in accordance with local, state and federal requirements.
<input type="checkbox"/>	<input type="checkbox"/>	Are mosquito or other insect habitats consistently present in the area as a result of the structure(s)?	Use appropriate mosquito insecticides or agents to control or eliminate insect breeding.

**MAINTENANCE LOG FOR
UNDERGROUND DETENTION FACILITY**

**UNIVERSITY CENTER
SETON HALL UNIVERSITY
SOUTH ORANGE, NEW JERSEY**

**INSTRUCTIONS:
THIS LOG SHALL BE UPDATED TO INCLUDE ALL MAINTENANCE
PERFORMED AT A SPECIFIC STORMWATER MANAGEMENT
MEASURE.**

DATE	PERSON CONDUCTING MAINTENANCE	AREA OF MAINTENANCE	PROBLEM(S) FOUND	ACTION(S) TAKEN

RECORD OF ANNUAL EVALUATION OF THE EFFECTIVENESS OF THE PLAN

**UNIVERSITY CENTER
SETON HALL UNIVERSITY
SOUTH ORANGE, NEW JERSEY**

**NOTE: EVALUATION TO BE CONDUCTED DURING A
PERIOD OF DRY AND WARM WEATHER AND LOW TIDE
CONDITIONS AT THE PROJECT SITE**

Evaluator(s)	Date of Evaluation	Decision
		<p>__Maintain current version OR</p> <p>__Revise current version</p> <p>Revision date _____ (also update the last revision date on the cover page)</p>
		<p>__Maintain current version OR</p> <p>__Revise current version</p> <p>Revision date _____ (also update the last revision date on the cover page)</p>
		<p>__Maintain current version OR</p> <p>__Revise current version</p> <p>Revision date _____ (also update the last revision date on the cover page)</p>
		<p>__Maintain current version OR</p> <p>__Revise current version</p> <p>Revision date _____ (also update the last revision date on the cover page)</p>